ITEM NO.	QUANTITY	DESCRIPTION OF EQUIPMENT	APPROVED MANUFACTURER	MECHANICAL												ITEM NO.	REMARKS (ALL ITEMS BY CHICK-FIL-A UNLESS OTHERWISE NOTED)
				ELECTRICAL						PLUMBING							
				VOLT	PH	KW	AMP	HP	NEMA-RATING	HW	CW	FW	FW2	IW	ROUGH-IN		
500AR	1	VERTICAL CONTACT TOASTER	EQUIPMENT TO BE REUSED/RELOCATED	120	1	1.8	15.0		5-15P							500AR	
500BR	1	RADIANT TOASTER	EQUIPMENT TO BE REUSED/RELOCATED	208	1	5.0	24.0		L6-30P							500BR	
500R	1	BUN WARMER	EQUIPMENT TO BE REUSED/RELOCATED	120	1	1.5	13		5-20P							500R	
505D	2	DOUBLE STACKED OVENS - ON STAND	BLODGETT MODEL #CTB	208	3	5.6	24/12/15		15-30P							505D	HINGE LEFT - MOUNTED ON 7" HIGH CART (3BLO004) WITH 6" CASTERS - ELECTRICIAN TO FIELD INSTALL ANGLE PLUG CORDSET
505G	1	RANGE/CONVECTION OVEN	LANG MODEL #9P-R30CAPF208CF	208	3	19.8	57.6		NEMA 15-60R							505G	HINGE LEFT - FULL GRIDDLE TOP - OVEN MOUNTED ON 4" CASTERS - E.C. TO PROVIDE 6' CORD & ANGLE PLUG
521	1	WARMING EYES	STAR-MAX MODEL #502FF	208	1	3.9	18.8		6-30P (BY E.C.)							521	LOCATED ON ITEM #521a - E.C. TO PROVIDE 6' CORD & PLUG
521a	1	WARMING EYES STAND	EAGLE MODEL #YCFA-0010-00													521a	ORDER WITH BRACKET #YJ-1750-00
522	1	OPEN FRYER	HENNY PENNY MODEL #CFE-410	208	3	22.0	61.0		PIN&SLEEVE							522	PIN&SLEEVE PROVIDED WITH EQUIPMENT AND RECEPTACLE BOX PROVIDED WITH HALTON ITEMS
522AR	1	DOUBLE OPEN FRYER	EQUIPMENT TO BE REUSED/RELOCATED	208	3	22.0/22.0	61/61		PIN&SLEEVE							522AR	
523	1	PRESSURE FRYER	HENNY PENNY MODEL #PFE-500	208	3	13.5	38.0		NEMA 15-50R							523	SUPPLIED WITH 6' SO CORD AND PLUG
523R	4	PRESSURE FRYER	EQUIPMENT TO BE REUSED/RELOCATED	208	3	13.5	38.0		15-50P							523R	
524R	2	DUAL-SIDED XPRESS BROILER	EQUIPMENT TO BE REUSED/RELOCATED	208	3	16.05	43.4/43.4/47.0		5-15P							524R	
550	2	DOUBLE WARMING DRAWER	STAR MODEL #7C-3B2DT09-CFA	120	1	0.9	7.83		5-15P							550	ON CASTERS - LOCATED UNDER ITEM #120 - FRANKE HOT HOLDING TABLE CIRCUITS #2 & #3
560	2	FRY HOLDING STATION	BKI MODEL #FW-15BB	120	1	1.84	15.4		5-20P							560	ON ITEM #105
563D	1	DOUBLE TIER SANDWICH SLIDE	BKI MODEL #2TSM-2624L	120	1	1.09	9.13		5-15P							563D	CORD EXITS LEFT - 6' CORD AND PLUG - PLACED ON ITEM 563Da
563Da	1	SANDWICH SLIDE STAND	CLAYTON FIXTURE													563Da	NOT SHOWN ON PLAN
563S	1	SINGLE TIER SANDWICH SLIDE	BKI MODEL #SM-2624R	120	1	0.548	4.56		5-15P							563S	CORD EXITS RIGHT - 6' CORD AND PLUG - PLACED ON ITEM 563Sa
563Sa	1	SANDWICH SLIDE STAND	CLAYTON FIXTURE													563Sa	NOT SHOWN ON PLAN
564	1	PRODUCT HOLDING CABINET	DUKE MODEL #FWM 3-24CF6-120	120	1	1.6	13.3		5-15P							564	PROVIDED WITH 5' CORD & PLUG
565C	1	FOOD COOKER/WARMER	ROUNDUP MODEL #CW-100	120	1	1.5	12.5		NEMA 5-15R							565C	ORDER WITH (1) 3VOL042, (2) 3VOL043, (8) 3VOL051, AND (8) 3VOL061
570	1	COOLING RACK	ADVANCED WIRE PRODUCTS LTD MODEL #RAK-1945													570	
580R	1	MULTI-USE HOLDING CABINET	EQUIPMENT TO BE REUSED/RELOCATED	120	1	2.88	24.0		L5-30P							580R	
581	1	DUMP CART	FRANKE CTS CART# 1B008028													581	
581R	1	DUMP CART	EQUIPMENT TO BE REUSED/RELOCATED													581R	
600	1	MIXER	HOBART MODEL #HL200	120	1		8.0	1/2	NEMA L5-20R							600	E.C. TO CHANGE PLUG TO TWIST LOCK - ORDER WITH 3HOB405, 3HOB061, 3HOB318, 3HOB319, & 3HOB058
600a	1	MIXER ROLLING CART	HOBART MODEL #HL2012													600a	ORDER ON 6" CASTERS
605	1	MOBILE CART	INTERMETRO MODEL #MW206													605	NOT SHOWN ON DRAWING; ORDER ON 5" CASTERS
606	1	JUICER WORK STATION	INTERMETRO													606	WITH (2) SOLID SHELVES AND 27 1/2" LEGS; ORDER (2) 2436FS; (4) 27PK3
607	1	Counter Top Lemon Juicer	Sunkist Model #J-1	115	1			1/4	5-15P							607	
620L	1	FOOD PREP TABLE	EAGLE MODEL #T2424STE-BS													620L	WITH BACKSPLASH - ORDER WITH 1 5/8" DIAMETER LEGS
624UB	1	FOOD PREP TABLE	EAGLE MODEL #T2448SE-BS													624UB	WITH UNDERSHELF & BACKSPLASH - ORDER ON 5" CASTERS
637M	1	FOOD PREP TABLE	EAGLE MODEL #T3066STEM-BS													637M	WITH MARINE EDGE & BACKSPLASH - ORDER ON 5" CASTERS
651P	5															651P	
651Pa	16	LOCKER ACCESSORIES	SALSBURY INDUSTRIES MODEL #77795 & #77760													651Pa	NOT SHOWN ON DRAWING - FACTORY INSTALLED LOCK W/RECESSED HASP - NAME NUMBER PLATES
654	3	WORK CHAIR	PROVIDED BY CHI													654	
655	2	FILE CABINET	HON MODEL #1626ML													655	2-DRAWER
656	1	DESK CHAIR	HON MODEL #7901AB10T													656	PROVIDED BY TRIMARK
660	6	PAPER TOWEL DISPENSER	SAN JAMAR MODEL #T1490TBK													660	RE: ARCHITECTURAL SHEETS FOR DETAILS ON MOUNTING HEIGHTS AND LOCATIONS
661	1	MOP RACK														661	FURNISHED BY OWNER
665	1	TRASH CART WITH LID	RUBBERMAID MODEL #1011 AND #1028													665	
669	1	OFFICE SAFE	TIDEL MODEL TITAN	120	1				5-20P							669	INSTALL SAFE PER MANUFACTURER'S WRITTEN INSTRUCTIONS
670R	1	SAFE	EQUIPMENT TO BE REUSED/RELOCATED													670R	
671	13	MENU BOX	C3 LIGHTING SOLUTIONS FLAT-VU	120	1	0.054	0.45		5-20P							671	
714	3	DUNNAGE RACK (22"x 48")	INTERMETRO - HP2248PDMB													714	
721FM	1	FLOOR SHELF UNIT (63" POST, 18"x30")	INTERMETRO													721FM	SOLID - 3 SHELVES
722N	1	FLOOR SHELF UNIT (74" POST, 18"x36")	INTERMETRO													722N	METROSEAL III - (3) 1836NK3; (4) 74PK3;(1) SF33N3K3
723H	1	FLOOR SHELF UNIT (86" POST, 18"x42")	INTERMETRO													723H	METROSEAL III - 5 SHELVES
723HW	2	FREEZER FLOOR SHELF UNIT (86" POST, 18"x42")	INTERMETRO													723HW	METROSEAL III - (5) 1842NK3, (4) 86PK3, (4) 9993S
724HW	1	FREEZER FLOOR SHELF UNIT (86" POST, 18"x48")	INTERMETRO													724HW	METROSEAL III - (5) 1848NK3, (4) 86PK3, (4) 9993S
732D	2	DRYING RACK (24"x36")	INTERMETRO													732D	METROMAX - (4) MX74P, (2) MX2436G, (2) M4F2436, (2) RPMX36-CBEAM, (2) DR36S, & (1) MTR2436XE
732Dd	1	STAINLESS STEEL SIDE PANEL	ATLANTA CUSTOM FABRICATORS (24"x68" W/HEMMED EDGE)													732Dd	INSTALLED ON #732D WITH HEMMED EDGE FACING AWAY FROM DRYING RACK
732H	1	FLOOR SHELF UNIT (86" POST, 24"x36")	INTERMETRO													732H	METROSEAL III - 3 SHELVES ABOVE DUNNAGE SHELF, 1 SHELF BELOW DUNNAGE SHELF
733HW	1	FREEZER FLOOR SHELF UNIT (86" POST, 24"x42")	INTERMETRO													733HW	METROSEAL III - (5) 2442NK3, (4) 86PK3, (4) 9993S
734H	2	FLOOR SHELF UNIT (86" POST, 24"x48")	INTERMETRO													734H	METROSEAL III - 3 SHELVES ABOVE DUNNAGE SHELF, 1 SHELF BELOW DUNNAGE SHELF
735H	1	FLOOR SHELF UNIT (86" POST, 24"x54")	INTERMETRO													735H	METROSEAL III - 5 SHELVES
735HT	1	FLOOR SHELF UNIT (84" POST, 24"x54")	INTERMETRO													735HT	METROSEAL III - 5 SHELVES; (1) DD9514
741U	1	GEN3 KIT (VEGGIE PREP)	INTERMETRO													741U	METROSEAL III - (1) 24"x48" SHELF + GEN3 COMPONENTS, (1) 48" GRID + UTILITY ACCESSORIES - SEE INTERIOR ELEVATIONS FOR MOUNTING INFO.
741V	1	GEN3 KIT (VEGGIE PREP)	INTERMETRO													741V	METROSEAL III - (1) 24"x48" SHELF + GEN3 COMPONENTS, (1) 48" GRID + VEGGIE PREP ACCESSORIES - SEE INTERIOR ELEVATIONS FOR MOUNTING INFO.
772	1	GEN3 SHELF (18"x36")	INTERMETRO													772	METROSEAL III - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
774	1	GEN3 SHELF (18"x48")	INTERMETRO													774	METROSEAL III - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
780	1	GEN3 SHELF (24"x24")	INTERMETRO													780	METROSEAL III - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
782	2	GEN3 SHELF (24"x36")	INTERMETRO													782	METROSEAL III - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
784	1	GEN3 SHELF (24"x48")	INTERMETRO													784	METROSEAL III - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
801	1	CONDIMENT RACK	INTERMETRO 24" X 48" GEN3 GRID + BINS													801	BRITE - ORDER (1) H210C, (24) SB91055CAS, (2) SB91587CAS
820	2	FLOOR SHELF UNIT (74" POST, 18"x24")	INTERMETRO													820	BRITE - 2 SHELVES ABOVE DUNNAGE SHELF, 1 SHELF BELOW DUNNAGE SHELF
822	2	FLOOR SHELF UNIT (74" POST, 18"x36")	INTERMETRO													822	BRITE - 2 SHELVES ABOVE DUNNAGE SHELF, 1 SHELF BELOW DUNNAGE SHELF
824	1	FLOOR SHELF UNIT (74" POST, 18"x48")	INTERMETRO													824	BRITE - 2 SHELVES ABOVE DUNNAGE SHELF, 1 SHELF BELOW DUNNAGE SHELF
832	1	FLOOR SHELF UNIT (74" POST, 24"x36")	INTERMETRO													832	BRITE - 2 SHELVES ABOVE DUNNAGE SHELF, 1 SHELF BELOW DUNNAGE SHELF
834	8	FLOOR SHELF UNIT (74" POST, 24"x48")	INTERMETRO													834	BRITE - 2 SHELVES ABOVE DUNNAGE SHELF, 1 SHELF BELOW DUNNAGE SHELF
834B	3	FLOOR SHELF UNIT (74" POST, 24"x48")	INTERMETRO													834B	BRITE - 3 SHELVES & BOTTOM DUNNAGE SHELF - LOCATED IN REFUSE ENCLOSURE STORAGE ROOM
835	1	FLOOR SHELF UNIT (74" POST, 24"x54")	INTERMETRO													835	BRITE - 4 SHELVES
851F	2	GEN3 SOLID SHELF (14"x30")	INTERMETRO													851F	BRITE - SOLID SHELF - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
851Fa	2	VERTICAL SHELF DIVIDER (8" HIGH X 14" DEEP)	INTERMETRO MODEL #DD14FC													851Fa	MOUNTED ON 12" CENTERS AT FOOD PREP AREA - NOT SHOWN ON PLAN
852F	2	GEN3 SOLID SHELF (14"x36")	INTERMETRO													852F	BRITE - SOLID SHELF - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
852Fa	4	VERTICAL SHELF DIVIDER (8" HIGH X 14" DEEP)	INTERMETRO MODEL #DD14FC													852Fa	MOUNTED ON 12" CENTERS AT FOOD PREP AREA - NOT SHOWN ON PLAN
854F	3	GEN3 SOLID SHELF (14"x48")	INTERMETRO													854F	SOLID - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
874	1	GEN3 SHELF (18"x48")	INTERMETRO													874	BRITE - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
874F	1	GEN3 SOLID SHELF (18"x48")	INTERMETRO													874F	SOLID - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
874S	4	SUSPENDED SHELF (18"x48")	INTERMETRO													874S	BRITE - SEE STRUCTURAL SHEETS FOR INSTALLATION INFORMATION
874Sa	12	VERTICAL SHELF DIVIDER (8" HIGH X 18" DEEP)	INTERMETRO MODEL #DD18K3													874Sa	MOUNTED ON 12" CENTERS - NOT SHOWN ON PLAN
874Sc	2	FLAT PLEXIGLASS PANEL	CUSTOM FABRICATION (48"x18"x1/4")													874Sc	MOUNTED TO ALUMINUM ANGLE BETWEEN #874S AND #894S AT SALAD PREP AREA
876S	1	SUSPENDED SHELF (18"x60")	INTERMETRO													876S	BRITE - SEE STRUCTURAL SHEETS FOR INSTALLATION INFORMATION
876Sa	4	VERTICAL SHELF DIVIDER (8" HIGH X 18" DEEP)	INTERMETRO MODEL #DD18K3													876Sa	MOUNTED ON 12" CENTERS - NOT SHOWN ON PLAN
881	2	GEN3 SHELF (24"x30")	INTERMETRO													881	BRITE - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
882	2	GEN3 SHELF (24"x36")	INTERMETRO													882	BRITE - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
882I	2	GEN3 INVERTED SHELF KIT (24"x36")	INTERMETRO													882I	BRITE - (1) 24"x36" SHELF; (1) 40" TRACK; (2) 12" UPRIGHTS; (2) INVERTED BRACKETS - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
883I	2	GEN3 INVERTED SHELF KIT (24"x42")	INTERMETRO													883I	BRITE - (1) 24"x42" SHELF; (1) 56" TRACK; (2) 12" UPRIGHTS; (2) INVERTED BRACKETS - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
884	5	GEN3 SHELF (24"x48")	INTERMETRO													884	BRITE - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
884I	2	GEN3 INVERTED SHELF KIT (24"x48")	INTERMETRO													884I	BRITE - (1) 24"x48" SHELF; (1) 56" TRACK; (2) 12" UPRIGHTS; (2) INVERTED BRACKETS - SEE INTERIOR ELEVATIONS FOR MOUNTING INFORMATION
884S	1	SUSPENDED SHELF (24"x48")	INTERMETRO													884S	BRITE - SEE STRUCTURAL SHEETS FOR INSTALLATION INFORMATION
886S	1	SUSPENDED SHELF (24"x60")	INTERMETRO													886S	BRITE - SEE STRUCTURAL SHEETS FOR INSTALLATION INFORMATION
892S	1	SUSPENDED SHELF (30"x36")	INTERMETRO													892S	BRITE - SEE STRUCTURAL SHEETS FOR INSTALLATION INFORMATION
894S	3	SUSPENDED SHELF (30"x48")	INTERMETRO													894S	BRITE - SEE STRUCTURAL SHEETS FOR INSTALLATION INFORMATION
896S	1	SUSPENDED SHELF (30"x60")	INTERMETRO													896S	BRITE - SEE STRUCTURAL SHEETS FOR INSTALLATION INFORMATION

FOR BID ONLY - NOT FOR CONSTRUCTION

Chick-fil-A
5200 Buffington Road
Atlanta, Georgia
30349-2998

TriMark
Foodservice Equipment, Supplies and Design
STRATEGIC

CHICK-FIL-A
Cherokee Place
Cartersville, GA

FSR# 00534

REVISION SCHEDULE

NO.	DATE	DESCRIPTION
4	01/31/18	Coordination Revisions

CURRENT TEMPLATE UPDATE APPLIED: NOVEMBER 2017
ARCHITECT'S PROJECT #: 00000
PRINTED FOR: PERMIT
DATE:
DRAWN BY: AMS

Information contained on this drawing and in all digital files produced for above named project may not be reproduced in any manner without express written or verbal consent from authorized project representatives.

PERMIT

SHEET: EQUIPMENT SCHEDULE

SHEET NUMBER: **K-202**

3/9/2018 3:38:54 PM